

Quotation/Tender
Name of Work- Construction of Growth Centre Goshni

To,

Deputy Project Director,
Watershed Management,
Integrated Livelihood Support Project,
Champawat.

Subject- Construction of Growth Centre (86Sq.m).

Reference- Letter No..... Dated.....

Sir,

We offer to execute the works described in your referred to above in accordance with the condition of Contract enclosed therewith.

Rs. (in figures)

Rs. (in words)

The quotation/tender and your written acceptance of it shall constitute a binding contract between us. We understand that you are not bound to accept the lowest or any quotation/tender you receive.

We hereby confirm that this quotation/Tender is valid for 45 days as required in Clause 4 of the instructions to Bidders.

Yours faithfully,

Authorized Signature :

Date:

Name & Title of Signatory :

Name of Bidder :

Address :

Section - B

BILL OF QUANTITY**Name of Work- Construction of Agribusiness Growth Center at Goshani (I.L.S.P) Champawat**

Si. No.	Item of work	Qty	DSR Chepter code	Unit	DSR	Cost of Index Champawat	Total Rate Including (GST)	Amount Rs.
1	2	3		4	5	8		10
1	R.C.C work in Column Including all Labour and material 1:1.5:3 20mm stone aggregate excluding centering and shuttering.	2.96	5.2	Cum	9306.00	2047.32	11353.32	33605.83
2	R.C.C work in First Floor Beam Including all Labour and material 1:1.5:3 20mm stone aggregate excluding centering and shuttering.	1.91	5.2	Cum	9306.00	2047.32	11353.32	21684.84
3	R.C.C 1:1.5:3 with 20mm stone aggregate in slab door bend Including all Labour and material Excluding centering and shuttering Etc.	14.31	5.3	Cum	9763.80	2148.04	11911.84	170458.43
4	Centering And Shuttering For Suspended Floors, Roofs, Landings Shelves, Balconies/Porch And Access Platform.	89.13	5.9.3	Sqm	693.05	152.47	845.52	75361.19
5	Centering And Shuttering For Lintels, Beams, Plinth Beams, Girders, Bressumers And Cantilevers.	16.60	5.9.5	Sqm	552.05	121.45	673.50	11180.10
6	Centering And Shuttering For door band	19.69	5.9.6	Sqm	733.70	161.41	895.11	17624.72
7	Centering And Shuttering For Columns,Pillars,Piers Abutments,Posts And Struts.	44.90	5.96	Sqm	733.70	161.41	895.11	40190.43
8	Ms Iron Work In Plain Works Such As Reinforcement , Brought To Required Shape As Necessary Including Supply Of All Material, Labour, T&P And Its Wastage Etc.. Required For Proper Completion Of The Work And As Per Direction Of Engineer-In-Charge.	1887.00	5.22.A	KG	82.10	18.06	100.16	189001.92
9	M - 150 Brick Work In 1:6 Cement And Fine Sand Mortar For One Brick Thick Wall In Super-Structure Including Supply Of All Material, Labour, T&P Etc. Required For Proper Completion Of The Work And As Directed By Engineer-In-	27.99	6.3.1	Cum	7722.65	1698.98	9421.63	263711.42
10	Plaster 12 Mm Minimum Thickness With Cement Mortar In 1:4 One Cement And Two Local Sand Minimum Thickness 1.25 Cm. Including Supply Of All Material, Labour, T&P Etc. Required For Proper Completion Of The Work And As Directed By Engineer-In-Charge. (Si367H)							
	Internal surface (F.F) /External surface Plaster	392.12	13.1.1	Sqm	266.85	58.71	325.56	127658.59
11	Two coat Oil Bond Distemper after prime coat Internal surface First floor .							
	Internal surface (F.F)	261.70	13.41.1	Sqm	153.45	33.76	187.21	48992.86
12	Two coat multi surface Paint after coat outer side Apex work (F.F)Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm							
	External surface (F.F)	130.42	13.48.1	Sqm	142.20	31.28	173.48	22625.26

13	Providing and laying vitrified floor tiles in different sizes (thickness to bespecified by the manufacturer) with water absorption less than 0.08% and 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete Size of Tile 600x600 mm	74.75	11.4	Sqm	1170.70	257.55	1428.25	106761.68
14	S/F Ceramic Wall Tiles 1:3 c/s motar	31.57	8.31	Sqm	1030.30	226.67	1256.97	39682.54
15	Sal Wood Wrought Framed And Fixed Including Simple Moldings Straight Work As In Chaukhats Including Supply Of All Materials, Labour, T&P Etc. Required For Proper Completion Of The Work And As Directed By Engineer-In-Charge.(Si 236H)	0.42	9.1.2	Cum	105327.20	23171.98	128499.18	53969.66
16	Supply And Fixing Of 40 mm Thick Second class teak wood Wood Shutters Fully Glazed/Gauged Shutter Including Supply And Fixing Of Wooden Cleats And Stops And Including Fixing And Adjustment Of Hinges, Bolts, Locks, Handles, Springs And Or Other Fittings But Excluding Their Supply And Painting With Two Coat Of Black Japan On All Iron Fittings If Necessary Also Including Supply Of All Material, Labour, T&P Etc. Required For Proper Completion Of The Work And As Directed By Engineer-In-Charge. (Si 246H)	7.61	9.7.1	Sqm	2942.30	647.31	3589.61	27316.93
17	Supply And Fixing Of 35 Mm Thick Commercial Quality Sitapur Shutters Or Of Any Other Equivalent Quality Including Supply And Fixing Of Wooden Cleats And Stops And Including Fixing And Adjustment Of Hinges, Bolts, Locks, Handles, Springs And / Or Other Fittings But Excluding Their Supply And Painting With Two Coat Of Black Japan On All Iron Fittings If Necessary Also Including Supply Of All Material, Labour, T&P Etc. Required For Proper Completion Of The Work And As Directed By Engineer-In-Charge.(Si 470P)	10.71	9.5.3	Sqm	3191.60	702.15	3893.75	41702.06
18	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture	18.74	13.48.2	Sqm	130.25	28.66	158.91	2977.97
19	Supply And Fixing Of M.S. Iron Grill As Per Design Weight Of Grill As Per Design Including S/O All Material, Labour, T&P Etc. Required For Proper Completion Of The Work And As Directed By Engineer-In-Charge.	136.98	9.48.1	KG	165.30	36.37	201.67	27624.75
20	With ready mixed red oxide zinc chromatic on steel / iron works having VOC content less than 50 grams/ liter.	12.17	13.85.1	Sqm	57.05	12.55	69.60	847.03
21	Finishing walls with water proofing cement paint of required shade.New work (Two or more coats applied @ 3.84 kg/10 sqm).	22.67	13.44.1	Sqm	91.25	20.08	111.33	2523.85
22	Supply And Fixing Of Glass Pans 4 Mm Thick On Window And Ventilators Including S/O All Material, Labour, T&P Etc. Required For Proper Completion Of The Work And As Directed By Engineer-in-Charge.	7.61	10.30.1	Sqm	900.55	198.12	1098.67	8360.87

23	Grading Roof For Water Proofing Treatment With Cement Concrete 1:2:4 (1 Cement : 2 Coarse Sand : 4 Graded Stone Aggregate 20 Mm Nominal Size) Including Water Proofing							
	Add Roof Slab	5.57	22.6	Cum	523.05	115.07	638.12	3554.32
24	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated 1.5 m, as directed by	1.85	2.61	Cum	181.85	40.01	221.86	410.44
25	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works							
	M.S. flat 50x6mm 2.4kg/per metre	162.91	10.25.1	KG	93.65	20.60	114.25	18612.46
26	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture.	5.09	13.48.3	Sqm	125.80	27.68	153.48	781.21
Total								1357221.35
Water Supply and Sanitary Service 1%								13572.00
Electrification 2%								27144.00
Contingency 3%								40716.00
Gross Total								1438653.35
Total								1438653.00

Signature/Stamp of contractor


 उप परियोजना निदेशक
 एकीकृत आजीविका सहायता परियोजना

Signature/Stamp
 Deputy Project Director,
 Watershed Management
 Integrated Livelihood Support Project
 Champawat

AGRIBUSINESS GROWTH CENTER - GOSHANI (ILSP CHAMPAWAT) :-

